



Steven W. Hurd, LLC dba
 Westwork Designs
 607 Davis Street
 Conway, Arkansas 72034

Proposal For Work:

Project:

Window sash/door transom restoration
 Rock Island Depot
 Perry, Arkansas

Work to be provided:

Restoration of existing window sashes/door transoms as noted below. Sashes to be removed for restoration and re-installed upon completion. Work to include, but not be limited to:

- Stripping of paint
- Disassembling sash frame as necessary
- Patching or replacing rail/stile as required
- Construction of new sash as required
- Reassembly and prepping for paint
- Re-glaze and prime
- Re-hang sashes

Window sashes/door transoms to be included in work as noted on included floor plan:

Sashes/Transoms

1. Transom	\$675.00
2. Double hung (DH) sashes with 2 broken panes.....	750.00
3. Transom with one broken pane.....	700.00
4. DH sashes with one or more damaged rails	1050.00
5. DH sashes. Bottom sash general restoration. Upper sash to be reconstructed from new and/or salvaged parts	1,250.00
6. DH sashes. Bottom sash general restoration. Upper sash to be reconstructed from new and/or salvaged parts	1,250.00
7. Transom with one broken pane.....	700.00
8. DH sashes.....	700.00
9. DH sashes with four broken panes	700.00
10. Bottom sash restoration/new upper sash.....	1,250.00
11. DH sashes with two broken panes	750.00
12. DH sashes with one broken pane	750.00
13. DH sashes.....	700.00
14. Transom	675.00

Total.....\$11,900.00

Notes on following page.

Notes:

1. Work to performed is for the window/transom sashes. Surrounding window frames are to be repaired by the Owner, if work is required.
2. Owner to provide filler panels in window openings during restoration.
3. Window sash weights are assumed to be remaining in the sash weight cavity. If they are missing, there will be an additional charge for required replacements.

Please let me know if you need any further information.

Sincerely,

Steve Hurd
Westwork Designs